



RAM JACK[®]

2013

CASE STUDY

Volume: 2013 | Issue: Swimming Pool Deck

**RESIDENTIAL SWIMMING POOL
DECK REPAIR**
Talladega, Alabama

six

Helical Piles &
Folding Slab
Brackets

THE POOL IS OPEN!
Concrete Slab Pool Deck
Recovered to Original
Elevation, All While
Keeping the Pool in Service

Alabama Ram Jack

www.alramjack.com | 877-875-2171

Bessemer, AL

CASE STUDY 2013



RESIDENTIAL SWIMMING POOL DECK

ALABAMA RAM JACK

BESSEMER, AL
877-875-2171
www.alramjack.com

A homeowner in Talladega, Alabama, received estimates to repair his below-grade swimming pool's concrete-slab deck which cracked and settled nearly three inches causing water to pond.

Situation

Estimates received from other companies were unsatisfactory because of the expense and disruption involved, as well as the lack of a suitable warranty. Based on a referral from an out-of-state friend, the owner finally contacted Ram Jack to find out if there was a better solution.

Solution

Alabama Ram Jack installed six helical piles through 10" diameter holes cored through the pool deck and applied fold-out slab brackets. The helical piles were used to lift the pool deck for full elevation recovery.

Conclusion

Alabama Ram Jack restored the swimming pool deck to its original condition at minimal expense and

disruption. The work was completed in two days, and the pool remained in service the entire time. Using quality materials and monitoring the installation torque/pressure ensured Ram Jack's ability to provide the owner with a lifetime guarantee against future downward movement.

*Concrete Slab Pool Deck
Recovered to Original
Elevation, All While
Keeping the Pool in Service*



www.ramjack.com/CaseStudies

Proven Engineered Solutions.

